TenderScope AI - Updated Tender Analysis Report

Tender ID: TDR-2554C1ACF7 | Re-analysis status: completed

Tender overview

Field	Value
Title	Supply of 11 kV, 3-Core, 240 mm² Aluminium XLPE Power Cable
Reference	WGPU/PROC/2026/SYN-011
Buyer	Westbridge Grid Projects Ltd.
Deadline	15 December 2026, 15:00 IST

Extracted mandatory requirements

Requirement	Value
Voltage	11 kV
Conductor	Aluminium
Cores	3
Cross-sectional area	240 mm²
Insulation	XLPE
Armour	Galvanized steel strip armour
Outer sheath	PVC ST2
Standard	IEC 60502-2

Required tests: Conductor DC resistance test; Insulation resistance test; High-voltage withstand test; Partial discharge test

Technical recommendations

SKU	Score	Compliance	Key result
AG-11-240-AL-STA	100%	Compliant	All mandatory parameters match.
AG-11-240-AL-SWA	87.5%	Non-compliant	Differences: Armour construction
AG-11-300-AL-STA	75%	Non-compliant	Differences: Cross-sectional area, Outer sheath material/grade

Pricing breakdown

Component	Basis	Cost
Material: AG-11-240-AL-STA	1200 x INR 485 per metre	INR 582,000
Test: Conductor DC resistance test	per_tender_lot	INR 4,000
Test: Insulation resistance test	per_tender_lot	INR 2,500
Test: High-voltage withstand test	per_tender_lot	INR 7,500
Test: Partial discharge test	per_tender_lot	INR 12,000

Component	Basis	Cost
Total estimated cost	Material plus all required tests	**INR 608,000**

Quality review

Status: **passed**. Missing information: 0. Unresolved requirements: 0.

Source references

AG-11-240-AL-STA: AGCS-DS-001, page 2; 02_Synthetic_Company_OEM_Product_Datasheets.pdf, page 2

AG-11-240-AL-SWA: AGCS-DS-002, page 3; 02_Synthetic_Company_OEM_Product_Datasheets.pdf, page 2

AG-11-300-AL-STA: AGCS-DS-003, page 4; 02_Synthetic_Company_OEM_Product_Datasheets.pdf, page 3; 02_Synthetic_Company_OEM_Product_Datasheets.pdf, page 2

Synthetic academic test data only. Not a commercial quotation or procurement recommendation.